


Status of CMS

The Compact Muon Solenoid Experiment at the LHC



Talk presented to HEPAP November 14, 2008 Joel Butler




Outline

- **1. Reminder: What is CMS**
- 2. The final push to install CMS
- 3. Activities from Sept 10 Sept 19 (beam)
- 4. Cosmic Run with Solenoid on (finished this week)
- 5. Plans for the remainder of the shutdown
- 6. Status of Production Computing Facilities
- 7. Status of Preparation for Physics
- 8. Upgrade plans
- 9. Some information about US CMS
- **10. Summary**



1. The CMS Detector





CMS Design Features

- Very large solenoid 6m diameter x 13 m long
 - Tracking and calorimetry fit inside the solenoid
 - Particle energies are measured before they pass through the solenoid coil and cryostat, which would degrade their resolution
- Very strong field 4T
 - Coils up soft charged particles
 - Provides excellent momentum resolution

Tracking chambers in the return iron track and identify muons

- This makes the system very compact
- Weight of CMS is dominated by all the steel and is 12,500 Tonnes

Tracking is based on all-silicon components

- A silicon pixel detector (with 68M pixels) out to ~ 20 cm
- A silicon microstrip detector (11M channels, 200M²) from there out to 1.2 m
- Gives CMS excellent charged particle tracking and primary and secondary reconstruction
- High segmentation results in very low occupancy
- Silicon detectors are very radiation hard

CMS was built on the surface. The pieces, some greater than 2000 Tonnes, were lowered into the Collision Hall. The Hall was made available late so installation did not begin until Nov 2006 and utilities did not appear until the spring of 2007




2. The Final Installation Push




Guido Tonelli, "For Opera lovers it has been our "Aida triumphal march" Dee 1 July 17 Dee 2 July 22 BPIX July 23-27 Dee 3 July 29 FPIX July 29-31 -- This is the last US piece of the Construction! Dee 4 August 1



Installation of ECAL Endcap Dees








Barrel & Forward Pixels










Minus End before Closure





Final Closure






3. Installation Status on September 10, 2008 and First Beam

- After almost 20 years, from conception, through design, construction and commissioning, CMS became a working experiment in September 2008
- At startup, the detector included
 - Barrel and endcap pixels
 - Si strip Tracker
 - Barrel and BOTH endcap ECALs!!!!
 - HCAL (barrel, endcap and forward)
 - Muons (DTs, CSCs and RPCs)
 - Level-1 Trigger, ~ 40 kHz DAQ
- Not available at startup
 - Endcap Electromagnetic Preshowers
 - Remaining capacity for Trigger/DAQ (deferred)
- For initial running with beam, the solenoid and the inner tracker were left off (machine issues)




First Events in CMS: Collimators Closed


~ 2.10⁹ protons on collimator ~150 m upstream of CMS



First Events: Beam going through CMS



Beam Pickup (ch1) CMS Beam Condition Monitors (ch 3, 4)



Point 5 Control Room


11111






4. Cosmic Run at Four (3.8) T - CRAFT

- CMS ran for 4 continuous weeks 24/7 (finished this week)
- We collected nearly 300M cosmic events with B=3.8T
 - •Showing that CMS was ready for the LHC
 - There are a wealth of lessons from this exercise...






Tracking rechits (green), ECAL rechits (pink), Reconstructed Muons (blue), DT 4D segments (red), DT chambers used in global Muon reconstruction (DT + Tracker) outlined with red, RPC rechits (green bars).



Another Craft Picture



HEPAP Nov. 14, 2008, Joel Butler



5. The Shutdown: Highest CMS Priorities

•Modifications to opening/closing system of wheels, disks and shielding

•safer opening/closing of CMS: reduce risk to detector and beam pipe.

•reduced exposure of personnel to activated parts.

•Modification to access platforms

•reduce risks to detector and beam pipe

•speed up changes

•Infrastructure (e.g. cooling, electrical power) diagnosis, repair and improvement to fix/reduce risk to detector, UXC access requirements and inefficiency (e.g. leaks, blockages, fan failures).

Repairs to achieve required 2009 performance (e.g. humidity seal, TK cooling plants)
Repair or re-work, necessary for final performance, in areas which will acquire significant activation. (ALARA)

•Preshower installation

•needs complex logistic set-up and thus long shutdown

•work area will acquire significant activation (ALARA)

•Set-up of full radiological screening and material tagging/classification/tracing for 2009 run.

The need to work around fragile beam pipe creates new problems



Overall strategy

•Plan

- •Start opening 17 Nov.
- •Preshower installation Feb.-Mar.
- •closed and operational end of May.
- •parallel shutdown and re-commissioning as soon as possible in 09
 - •Make limited cooling and power re-available as soon as possible to test new or repaired items

The biggest uncertainty in all this is the LHC schedule



Shutdown 2008-9: Schedule overview

	Activity Name		Sept08 Oct08						Nov08 Dec08							Jan09 Feb0					09) Mar09						Apr09					May09			Jur	Jun09	
			21	28	5	12	19	26	2	9 '	16 2	3 30) 7	14	21	28	4	11 18	25	1	8	15	22	1	8	15	22	29	5	12	19	26	3	10	17	24 3	81 7	14
1	Remove CASTOR, secure problem objects.				Č	-																																
	Establish magnet operation at 3.8 T.				Z	3																																
3	De-classify cavern (Gamma spectroscopy).					58																																
4	Ramp to 3.8T under survey.					4																																
5	CRAFT							ecci.	222																													
	Shielding completion									5																												
7	Ramp to 3.8T then 4T. Survey, Mag measurements									0																												
	Fast discharge from 3.8 T									կ																												
9	Open Rotating shielding, remove wedges (concreting)									18	C	om	olete	ma	gne	t te	sts																					
	Preparation for opening + yoke (bp, survey etc)										222																											
	HF garage. Open + end, CSC, DT, RPC.											eien	X I	hase	e 1																							
12	Surkov frame + z in place. TK, EB, HB															_	_		-	-						+END												
13	YE+closed,YB0+ & YB+1,2 access. CSC,DT,RPC												***	***	_		XXX	XXXXX																				
14	Close YB+ barrel, DT,RPC.																	-	ĸĸĸ	xxxx	🛛 Pl	hase	2															
15	Install 20t table & pixel platform																				- 332																	
16	ES+ installation, fpix removal/insertion,TK PP maint.																					**	***	****	***	****			se 3	3								
	Remove 20table and pixel platform																										- 5	552										
18	Close YE+z endcaps, CSC,RPC																											ł	XX	- 🖾		ъ	hase	. 1				
	HF +z to beam height, install TOTEM T1																													Ø			nase	:4				
	Preparation for opening - yoke (bp, survey etc)												E	222																								
21	HF garage. Open - end. CSC, DT, RPC.														L		XXX	SS Pl	iase	1										-								
	Surkov frame -z in place																		-	-								-	ΕN	JI.)							
	YE- closed, YB0- and YB-1,2 access																	222	8888)		1																	
	Close YB- barrel, DT,RPC.																				XXX	()())	***	Pha	se 2	2												
	Install 20t table & pixel platform																						Z	22														
	ES- installation, fpix removal/insertion,TK PP maint.																							×	XXX		XXX	000	XXX	$^{\rm Ph}$	ase	3						
27	Remove 20t table and pixel platform																													- 33								
	Close YE-z endcaps, CSC,RPC																														lĒ	XX						
	29 HF -z to beam height, install T1																															Ð	****	S1				
	30 Magnet test to compress yoke																																	-6	Phas	e 4		
31	Install T2, CASTOR , close HF- & forward shielding																																	5	XX			
32	Install T2, close HF+ & forward shielding																																		ĸ	X P	hase	5
	Re-commissionng with magnet on																																				cecer	
34																																		29	9 Ma	y 20	09	
35	Trcaker cooling plant upgrade																																					
		14	21	28	5	12	19	26	2	9 '	16 2	3 30) 7	14	21	28	4	11 18	25	1	8	15	22	1	8	15	22	29	5	12	19	26	3	10	17	24 3	31 7	14




Status of the Preshower

All 520 ladders assembled and stress-tested

Ladders mounted, cabled and tested on 4 of 8 absorbers. All channels (~50k silicon strips) operational. First two stuffed absorbers tested inside an environment-controlled

tent to -15 °C (in the old "TIF")

Target: get ES 'ready for installation' by the end of 2008




ES prior to moving the absorber into the tent HEPAP Nov. 14, 2008, Joel Butler

18



6. CMS Computing Model

- Reminder of CMS Computing Model:
 - user submit jobs, workload management system submits to where data is
 - data movements are triggered by operators, physics organizers, users





Computing Infrastructure: Tier-1

- Fermilab Tier-1 has reached goals of a four-year procurement ramp
 - Meeting the obligations of the U.S. to CMS Computing and providing analysis resources for the LHC Physics Center at Fermilab
 - met WLCG milestone for completion of the 2008 pledge
 - Part of the worker node early purchase for FY09 is complete
 - division between Tier-1 and LPC CPU resources
 - well defined through batch slots, but operationally flexible
 - Recently allocated a larger fraction to Tier-1 to support scale testing and cosmic re-reconstruction

FNAL	Tier-1+LPC	7500 Batch Slots	Processing Nodes
	Tier-1+LPC	11MSI2k	Processing Capacity
and	Nominal Split	5100 T1, 2400 LPC	
LPC	Disk T1	2.0PB	dCache (1600MB/s IO)
Summer 2008	Disk LPC	0.5PB	Dedicated to Local Analysis
2000	Network	20Gb/s	CERN to FNAL
	People	30FTE	Includes Developers and Ops




Computing Infrastructure: Tier-2s

- U.S. Tier-2s extensively used for simulation and analysis
 - all SEVEN the US Tier-2 sites reached nominal capacity this summer
 - FY09 Tier-2 ramp to double storage and increase CPU by 50%
- Tier-2 program great success thanks to very engaged sites
- Organized sites in CMS to support physics analysis for users
 - associated sites with specific physics/detector performance groups
 - allocated disk space for groups, and disk space for individual users

US-CMS	CPU T2	1MSI2k	Tier-2 Processing Nodes
	Disk T2	200TB	dCache (200MB/s IO)
Summer 2008	Network	2.5-10Gb/s	WAN Networking
	People	2FTE	Supported Tier-2 Operations



Moving the Data Around






7. Preparations for Physics

Strong emphasis on integration of the efforts of


- groups working on commissioning and understanding the detector (Data Performance Groups or "DPGs")
- groups developing Physics Objects (photons, electrons, muons, taus, jets, missing Et, etc) for analysis ("POGs")
- groups extracting physics (Physics Analysis Groups or "PAGs")
- Strong emphasis on what can be done with "early" physics samples of 10 pb⁻¹, 100 pb⁻¹, and 1000 pb⁻¹.



CMS Physics Organization



The Excitement of a New Energy Frontier





8. Luminosity Upgrade: Issues for CMS

- PHASE 1 to start in 2013 with L= 2-4 × 10³⁴ cm⁻² s⁻¹
 PHASE 2 to be decided in 2011 with L=8-10 × 10³⁴ cm⁻² s⁻¹
- US-CMS upgrade plan based on the detector needs to run for sustained periods at luminosities well above 10³⁴cm⁻²s⁻¹
- Issues that must be addressed
 - Radiation damage
 - High occupancy affecting reconstruction or triggering
 - High occupancy that leads to buffer overflows and to problems with link bandwidth
 - Pileup creating dead time or affecting trigger
 - CMS is accessible, has been designed to be opened, and therefore "easy" to upgrade
- Upgrade R&D is now ramping up to deal with collision rates that are well beyond the requirements of the original detectors. Detailed upgrade plans are being developed



CMS Phase 1 Upgrade

- An initial plan for CMS is being developed and the corresponding US component of it has been presented to DOE and NSF
- Upgrade includes
 - Pixel replacement (radiation damage, buffer overflows)
 - Hadron Calorimeter increase longitudinal segmentation to deal with radiation damage and add timing
 - Muon
 - Trigger/DAQ
 - Electromagnetic calorimeter

A CMS workshop will take place from Nov 19-21 at Fermilab to develop the Phase 1 Upgrade



9. US Leadership Positions in CMS

CMS

- Robert Cousins (UCLA): Deputy Spokesperson since 1/07
- Dan Green (FNAL): Chair CMS Collaboration Board starting 1/09
- Joe Incandela (UCSB): Deputy Physics Coordinator
- Trigger Coordinator: W. Smith (Wisc)
- Deputy Run Coordinator: D. Acosta (Fla)
- Deputy Computing Coordinator: P. Mcbride (FNAL)
- Physics Convenors
 - Higgs: A Korytov (Fla)
 - SUSY; J Richman (UCSB)
 - Exotica: G. Landsberg (Brown)
 - Top: C. Campagnari (UCSB)
 - Heavy lons: G. Roland (MIT)
 - QCD: N. Verelas (UIC), V. Odell (FNAL)
 - EWK: S. Dasu (Wisc)
- Detector Project Managers
 - HCAL: A. Skuja (Maryland)/J. Spalding (FNAL)
 - ECAL: R. Rusack (Minn)
 - Endcap Muons: R. Loveless (Wisc)



USCMS in the CMS Collaboration

CMS


- 39 Countries
- 181 Institutions
- 1940 Scientific Authors total
- 1283 paying M&O share

USCMS

- 639 Scientific Authors
- 442 with Ph.D (34.5%)
- 197 Graduate Students



- US CMS full time people at CERN
 - A 26 Professors
 - 16 Scientists
 - 57 Post Docs
 - ♦ 86 Graduate Students
 - 24 Professionals
 - 4 Technicians
 - 4 staff
- 217 total





Summary

- After 20 years of planning and an incredible "finishing kick" in July, CMS was closed and ready for first beam
- During the limited beam, collimator "splash events" and circulating beam "halo events" were recorded and are being analyzed to extract all possible information on the detector
- After the shutdown, a month of highly successful Cosmic Running with the CMS Solenoid on at 3.8T was completed and analysis is already in full swing
- A thoughtful, focused and flexible plan of improvement is planned for the remainder of the shutdown
- CMS is continuing to prepare for the physics analysis of the early runs
- Upgrade planning and R&D are in full swing
- A large US community, about 1/3 of total is resident at CERN, while the remaining 2/3 is actively engaged from the US
- We eagerly await first collisions!!!!







Elective activities

- •Non-critical repairs which allow untried routine maintenance procedures to be tested, (especially if work area will acquire activation)
- Non-critical new installation, repairs or improvements which can be done off the critical path.
- Non-critical new installation, repairs or improvements not subject to ALARA which require a long shutdown.

all subject to availability of resources after highest priorities satisfied


•All CMS systems (except BCM!) have made intervention requests. see TCM 09 Oct : http://indico.cern.ch/conferenceDisplay.py?confId=42919 -priority, required configuration and resources for each are being discussed in TCM/TIG, MTP,EB,MB meetings. -final decisions on priority and time allocation once we have a sound framework

planning (many activities can be don e parasitically to CP)




First Events: Collimators Closed

~2.10⁹ protons on collimator ~150 m upstream of CMS ECAL- pink; HB,HE - light blue; HO,HF - dark blue; Muon DT - green; Tracker Off





CRAFT statistics





- 360 M-cosmic events all over
- 290 M-cosmic events with DT / B-magnet / StripTK in
 - about 3% have Tracks into it




Tier-2 MC Production Metric

- CMS has been running grid enabled MC production for 5 years
 - This month CMS achieved the nominal rate of more than 100M ev./month
 - 35 Tier-2s contributed worldwide
 - seven U.S. Tier-2 are top performers
 - <1 FTE US effort to run the system</p>






 \sim 6-10k batch slots





US Computing Sites

- US sites are working well and ramping up
 - Contributing both to central simulation (upper plot) and user analysis (lower plot)
 - OSG Providing more than nominal 35% US share for simulation
 - **Computing Commissioning program** ٠ ramping functional Tier-2s for analysis
 - 7 Strong Tier-2s at US Universities



ucr.edu

submitted app-succeeded app-failed app-unknown

2500

5000

7500

number of jobs

10000

pending running aborted cancelled

FZK-LCG2 (Karlsruhe, Germany)-



12500



Assembly of ECAL Endcap Dees



